



600 Wabash Ave.  
Terre Haute, IN 47807  
812.234.5190  
812.234.7346 Fax

**PROJECT:** Indiana State University  
Science South Elevator

**PROJECT NUMBER:** 12.035

**DATE:** 01.30.13

**PREPARED BY:** Curt Schriener

## **ADDENDUM**

---

Number: TWO

This Addendum is issued in accordance with the provisions of "The General Conditions of the Contract for Construction," Article 1, " Contract Documents " and becomes a part of the Contract Documents as provided therein. This Addendum includes:

- A. Addendum Pages: ADD2-1 through ADD2-1 as prepared by MMS-A/E, Inc.
- B. Attachments: Questions & Answers

### **PART 1 - BIDDING & CONTRACT REQUIREMENTS**

1.01 n.a.

### **PART 2 - SPECIFICATIONS**

2.01 n.a.

### **PART 3 - DRAWINGS**

3.01 n.a.

ADD 1-1

Please acknowledge receipt of Addendum No. 1 on bid form.

## QUESTION AND ANSWERS:

- Q1. Where are the starting and stopping points for painting?
- A1. Paint south facing walls only, as well as surfaces shown on A601.
- Q2. Please clarify the demolition of the elevator, elevator equipment, and rails must be by a licensed elevator contractor.
- A2. Utilize a licensed elevator contractor to disconnect and lower the elevator. The G.C. will be allowed to demolish the remaining cab, rails, equipment, etc. thereafter.
- Q3. Is there a current pit in the shaft and do we need to put a pump in it or do we need to install a new pit and pump with associated plumbing and electrical? If this is correct, can you provide some details of the new sump pit?
- A3. There is an existing sump pit with pump and associated piping below the existing passenger elevator. This pit gets filled in and the pump and piping gets removed and capped off. There will need to be a new pit formed and located as shown on the drawings below the new elevator. Sump pump and piping is not needed, just the pit.
- Q4. Will we be able to use a gas powered buggy to haul concrete?
- A4. Gas powered buggies will not be allowed within 8' of the building's entry
- Q5. Is the hardware allowance a material allowance or labor and material allowance?
- A5. The hardware allowance is for purchase of hardware only. Labor for installation should be included in base bid.
- Q6. The floor plan indicates expansion joints however I didn't see a specification section for this. Please clarify.
- A6. Use basis of design for the expansion joint material as described in division 032130. The expansion joint cover was sent in addendum 1.
- Q7. The specifications indicate "Fire Protection Division-21" is not used, however the prints indicate that there is sprinkler work due to the new architectural layout. Could you please clarify this scope of work?
- A7. There is no new Fire Protection needed. This was a cover all for unforeseen conditions.