



600 Wabash Ave.
Terre Haute, IN 47807
812.234.5190
812.234.7346 Fax

PROJECT: Indiana State University
Science South Elevator

PROJECT NUMBER: 12.035

DATE: 02.01.13

PREPARED BY: Curt Schriener

ADDENDUM

Number: THREE

This Addendum is issued in accordance with the provisions of "The General Conditions of the Contract for Construction," Article 1, " Contract Documents " and becomes a part of the Contract Documents as provided therein. This Addendum includes:

- A. Addendum Pages: ADD3-1 through ADD3-1 as prepared by MMS-A/E, Inc.
- B. Attachments: Questions & Answers

PART 1 - BIDDING & CONTRACT REQUIREMENTS

1.01 n.a.

PART 2 - SPECIFICATIONS

2.01 n.a.

PART 3 - DRAWINGS

3.01 n.a.

ADD 1-1

Please acknowledge receipt of Addendum No. 1 on bid form.

QUESTION AND ANSWERS:

- Q1. Can Abbell International's elevator equipment be used in this project?
- A1. Abbell International's request for substitution is not approved and elevator equipment by Abbell International shall not be used for submission of a Bid on this Project.
- Q2. Shown on the drawings are steel lintels. Should we use what is listed (3 ½" x 8' x ¼") or will this need to be a steel angle or weld a stiffener to the center and notch the block? Please advise.
- A2. Follow the lintel schedule on A601, utilizing the precast concrete lintels in lieu of the steel lintels on the drawings.
- Q3. The specifications indicate "Fire Protection Division-21" is not used, however the prints indicate that there is sprinkler work due to the new architectural layout. Could you please clarify this scope of work?
- A3. ~~There is no new Fire Protection needed. This was a cover all for unforeseen conditions.~~
Correction: There will need to be fire sprinkler work done on each floor, branching off of the 2 ½" main, passing through the 4" block wall and dropping down into the lobby with a new sprinkler head. The third floor will need to have additional drywall demo, patching, and painting done to access the fire main. The entire bulkhead will need to be repainted so the color is consistent throughout.